

15-167-20394-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Dreiling & Borrell

Complete Address R. R. # 2, Victoria, Kansas

Lease Name Eschboug "B" Well No. # 1

Location SE SE SE Sec. 11 Twp. 14 Rge. 11 (E) (W) W

County Russell Total Depth 2973

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Same (Co. tools)

Address Same License No.       

Operation Completed: Hour 5 A.M. Day 10 Month 2 Year 1970

The above well was plugged as follows:

8 5/8" 305' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax cement thru

drill pipe. Mud to 300' & displaced 25 sax cement thru drill pipe. Mud to 40',

1/2 sax hulls, plug, & displaced 10 sax cement with Sun Cementing Company's pump

truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

RECORDED  
DATE 2/12/70  
INV. NO. 1415-W