

KANSAS

FORM CP-3
Rev, 11-3-80



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21,565-0900

245 North Water
Wichita, KS 67202

Operator's Full Name Custom Oil Explorations, Inc.

Complete Address P. O. Box 305, Chase, Kansas 67524

Lease Name Charvat Well No. 1

Location N $\frac{1}{2}$ W $\frac{1}{2}$ NW $\frac{1}{4}$ Sec. 3 Twp. 14S Rge. 11 (~~East~~) (West)

County Russell Total Depth 3020'

Abandoned Oil Well Gas Well Input Well SWD Well D & A (Lost Hole)

Other well as hereafter indicated Lost Hole.

Plugging Contractor Co Tools & Sun Cementing Co.

Address P O Box 305, Chase, Kansas 67524 License No. _____

Operation Completed: Hour 8:05 Day 18 Month 11 Year 1980
PM

The above well was plugged as follows:

_____ Filled hole with mud and spotted 55 sx cement at 480'.

_____ Filled hole with mud and spotted 30 sx cement at 240'.

_____ Filled hole with mud to 40' and $\frac{1}{2}$ sx hulls, plug, and
10 sx cement to bottom of celler.

_____ 5 sx cement in rat hole.

_____ Twisted off drill pipe, and left aprox. 1800' of 4 $\frac{1}{2}$ " drill
pipe in the hole. Top of drill pipe at aprox 1212'.

_____ 300' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

Signed: Duane R. Rankin
Conservation Division Agent

11-25-80

12-12-80
3759-W