

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-051-22,172-00-00 (of this well) 6/88  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Dreiling Ltd. of Colorado OPERATORS LICENSE NO. 5804  
ADDRESS 410 17th St., Ste. 1140 Denver, CO 80202 PHONE # (303) 623-6144  
LEASE (FARM) C. Lang WELL NO. 1 WELL LOCATION SEENW COUNTY Ellis  
SEC. 6 TWP. 14S RGE. 17 ~~(S)~~ (W) TOTAL DEPTH 3635 PLUG BACK TO 3605

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_  
SURFACE CASING SIZE 8-5/8 SET AT 290 CEMENTED WITH 160 SACKS  
CASING SIZE 5-1/2 SET AT 3633 CEMENTED WITH 1st 150/ 2nd 275 SACKS  
PERFORATED AT 3354'-3377', 3564'-3584', 3586'-3591'/ Bridge plug at 3558'

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL F.O. tool at approx. 1250'; 5-12" casing cemented from 1250' to surface w/ 275 sks. of cement. Plug with 200 sks. light cement 65/35 Pozmix w/ 10% gel; load and pressure both annulus and casing with cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? KCC already has a copy IS ACO-1 FILED? yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dave Dreiling PHONE # (913) 625-5230

ADDRESS P.O. Bos 223 Hays, KS 67601

PLUGGING CONTRACTOR Halliburton LICENSE NO. 5287 11-13-87

ADDRESS Hays, KS 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]  
(Operator or Agent)

DATE: 11-2-87

④

State of Kansas



15-051-22172-00-00

Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

FEB 17 '88

EXPIRES

November 17, 1987  
WELL PLUGGING NOTICE

C. Lang #1  
SE NE NW  
Sec. 06-14S-17W  
Ellis County

Dreiling Ltd. of Colorado  
410 17th Street, Ste. 1140  
Denver, CO 80202


Gentlemen: .

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 66720 (913) 628-1200

CHANGE OF OPERATOR

15-051-22172-00-00

=====

Previously operated by:

Dreiling Ltd. of Colorado  
410 - 17th Street, Suite 1140  
Denver, CO 80202  
Operator license # 5804

Currently operated by: (effective January 15, 1988)

C and R Drilling Company  
410 - 17th Street, Suite 1140  
Denver, CO 80202  
Operator license # 5815