

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-23, 199-66-00

C-5 1/2 N 1/2 NW, Sec. 1, T 14 S, R 16 W/E

\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6246

Lease Name SCHULTE Well # A-1

Operator: BENNETT + SCHULTE  
Name & OIL CO.  
Address BOX 329  
RUSSELL, KANS.  
67665

County ELLIS  
Well Total Depth 3440 feet  
Conductor Pipe: Size - feet -  
Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor LABANCO DRILLING License Number 458

Address BOX 289 NATOMA, KANS. 67651

Company to plug at: Hour: 11:00 AM Day: 17 Month: OCT Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO JOHN WEIS

(company name) LABANCO DRILLING (phone) 913-885-4676

were: 8 5/8" - 284 FT SP. CUC. w/ 175 ST QUICK SET. (BY ALLIED OMT)

ORDER 180 ST 50/50 FORMIX 4% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG @ 3410 FT w/ 20 ST CMT. -> 2<sup>ND</sup> PLUG @ 1020 FT w/ 20 ST CMT.

3<sup>RD</sup> PLUG @ 660 FT w/ 80 ST CMT. -> 4<sup>TH</sup> PLUG @ 300 FT w/ 40 ST CMT.

5<sup>TH</sup> PLUG <sup>SOLID BRIDGE</sup> HULLS - PLUG @ 40 FT w/ 10 ST CMT.

10 ST IN RAT HOLE. (CIRCULATE)

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:30 PM Day: 17 Month: OCT Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 284 FT SP. CUC. (BY ALLIED OMT.)

ORDERED 180 ST 50/50 FORMIX 4% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG @ 3410 FT w/ 20 ST CMT. -> 2<sup>ND</sup> PLUG @ 1020 FT w/ 20 ST CMT.

3<sup>RD</sup> PLUG @ 660 FT w/ 80 ST CMT. 4<sup>TH</sup> PLUG @ 300 FT w/ 40 ST CMT.

5<sup>TH</sup> PLUG - <sup>SOLID BRIDGE</sup> HULLS - PLUG @ 40 FT w/ 10 ST CMT. -> 10 ST IN RAT HOLE

(CIRCULATE)

Remarks: CEMENTED BY ALLIED OMT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1982

CONSERVATION DIVISION  
Wichita Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

INVOICED  
DATE 11-9-82  
INV. NO. 1525-W(A)

Signed [Signature]  
(TECHNICIAN)