

242
K

4-24

6090436

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,638-00-00

NE NW SE 1/4 (SEC. 06, 14 S, 17 W)
2310 feet from S section line
1650 feet from E section line

Operator license#5886 Lease FCU well #1-6

Operator: Chief Drilling Company, Inc County Ellis

Address: 224 E. Douglas, #530 Well total depth 3600 feet ^{117.00}
Wichita, Kansas 67202 Conductor Pipe: - inch @ - feet
(316)262-3791 Surface pipe 8 5/8 Inch @ 274 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Warrior Drilling Company License#5883

Address: Wichita, Kansas 67202

Company to plug at: Hour: AM Day: 23 Month: April Year: 1990

Plugging proposal received from: Marion Burris

Company: Warrior Drilling Company phone: (316)262-3791

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3540 feet with 20 sacks Rat hole: 15 sacks

2nd plug @ 1225 feet " 20 " Mousehole: 10 sacks

3rd plug @ 580 feet " 100 "

4th plug @ 40 feet " 10 " & wiper plug

5th plug @ feet

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 7:45 AM, Day: 24, Month: April, Year: 1990

Actual plugging report: Hole reported plugged as above.

Order 175 sx 60/40 Pozmix w/ 6% gel and 1 sx celloflake or flowcel

Remarks: Elevation: 2004' GL, Anhydrite depth: 1210' - feet
⁰⁵⁻⁰³⁻⁹⁰

Did penetrate Arbuckle, cemented by Allied Cementing Company

I did / did not X observe the plugging.

Edwin A. Schumacher
Edwin A. Schumacher
(agent)

DATE 5-7-90

INV. NO. 28036

Ed. S.

INVOICED