

1-12-88

To: 6 970625
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-22,172-00-00

SE NE NW SEC. 6, T 14 S, R 17 W/4
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Lease Name C. Lang Well # 1

Operator: Dreiling LTD of Colorado
Name & Address 410 17th Street #1140
Denver, Colorado 80202

County Ellis 118.14

Well Total Depth 3635 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement Co. License Number _____

Address East Hwy 40 Hays, Kansas

Company to plug at: Hour: 1:00 PM Day: 12 Month: Jan Year: 19 88

Plugging proposal received from Dave Dreiling

(company name) Dreiling L.T.D. of Colorado (phone) _____

were: 8 5/8" 209' S.P. cwc w/160 sks. 5 1/2" csg set at 3633' w/150

sks cmt. F.O. Tool at 1250' cwc w/275 sks cmt. No pipe recovery. PBSD 3605'.

Perfs 3354' to 3591'. Proposal 200 sks 65/35 Poz 10% Gel and 5 sks Hulls.

Procedure: Load and pressure annulus with cement. In 5 1/2" csg, load and pressure csg with cement.

_____ Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 PM Day: 12 Month: Jan Year: 19 88

ACTUAL PLUGGING REPORT _____ Ordered 210 sks 65/35 Poz 10% Gel (Econolite) and five

(5) sks of Hulls pumped in with pump truck. Pumped in annulus 5 sks cmt. Max Psig.

800. Shut in at 800 Psig. Pumped in 5 1/2" csg 205 sks cmt with Hulls. Max pressure

300 Psig. Shut in at 300 Psig. Cemented by Halliburton Cement.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICE serve this plugging.

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

DATE 1-26-88

INV. NO. 19659