

To: **6 070650**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-10-88 132
R
API NUMBER 15- 051-22,455-00-00
NW SE NW SEC. 6, T 14 S, R 17 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Lease Name _____ Lang _____ Well # 2-C

Operator: Dreiling L.T.D. of Colorado
Name & Address _____
410 17th Suite 1140
Denver, Colorado 80202

County Ellis 118.63

Well Total Depth 3650 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well RECEIVED D&A

Other well as hereinafter indicated _____ STATE CORPORATION COMMISSION

Plugging Contractor Allied Cementing Co. License Number APR 2-2-1988

Address Box 31, Russell, Kansas 67665 04-22-88

Company to plug at: Hour: 10:00AM Day: 10 Month: Mar CONSERVATION DIVISION
Wichita, Kansas 88

Plugging proposal received from Dave Dreiling and Gary Geist

(company name) Dreiling L.T.D. and Midwestern Pipe Works (phone) 913-625-4670

were: 8 5/8" - 285' S.P. cwc w/160 sks cement; 4 1/2" csg set at 3518' w/150 sks cement.

Plug back 3618'; Perf 3400' - 3404' - 3346' - 3350'. Plugged off bottom of 4 1/2" csg to 3300'
and w/5 sks cement. Pulled csg into at 600'. Recovered 600'. Proposal 50 sks Class A Cement
and 150 sks A.T.L. 65/35 Poz 10% Gel 5 sks Hulls. Perferate anhydrite at 1155'. Run tubing
to 1137'. Spot Class A Cement, then 150 sks A.T.L. and squeeze.

Plugging Proposal Received by M. J. S. (TECHNICIAN) *MJS*

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:40AM Day: 10 Month: Mar Year: 19 88

ACTUAL PLUGGING REPORT Ordered 50 sks Class A Cement and 150 sks A.T.L. 65/35 Poz

10% Gel and 5 sks Hulls. Perferated at 1155'. Spotted with tubing.

1) Spotted 50 sks Class A Cement at 1137'; 2) Spotted 75 sks A.T.L. at 450' Cement
circulated. Then, squeezed csg with another 75 sks cement with 4 sks Hulls added. Max
pressure 900 Psig. Shut in at 700 Psig. Cemented by Allied Cementing, Russell, Kansas

Remarks: _____ (If additional description is necessary, use BACK of this form.)

INVOICED
DATE 4-26-88
INV. NO. 20439

Signed Marion V. Schmidt (TECHNICIAN)