

4-090529

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 N. MARKET - ROOM #2078  
WICHITA, KANSAS 67202

API number: 15-167-23,091-00-00

NE SW NW /4 SEC. 13, 14 S, 13 W  
3630 feet from S section line  
2970 feet from E section line

Operator license# 6246 Lease Rein well # 4

Operator: Bennett & Schulte Oil County Russell

Address: P.O. Box 239 Well total depth 3057 feet  
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 428 feet

99.35

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: L & M Well Servicing, Inc. License# 31172

Address: P.O. Box 528 - Russell, Kansas 67665

Company to plug at: Hour:     -     Day: 7 Month: April Year: 95

Plugging proposal received from: Arnie Michaelis

Company: L & M Well Servicing, Inc. Phone: 913-483-2041

Were: Order 250 sxs. 60/40 posmix - 10% gel - 500# hulls.  
Total cement used 265 sxs. 60/40 posmix - 10% gel.

APR 17 1995  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
04-14-95

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 2:10 P.M., Day: 7, Month: April, Year: 95

Actual plugging report: 8 5/8" to 428', 5 1/2" to 2619'. Plug back to 2410' with sand and spotted 5 sxs. cement with dump bailer. Shot casing at 1650'. Mixed and pumped 110 sxs. cement with 300# hulls at 1470'. Pulled casing to 840' and pumped 30 sxs. cement with 100# hulls. Pulled casing to 440' and pumped 80 sxs. cement with 100# hulls and circulated cement to surface. Pulled casing and topped with 15 sxs. cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation: 1830 GL

I did X did not[     ] observe the plugging. Ed Schumacher

DATE 4-21-95

(agent)  
Form CP-2/3

INV. NO. 42653 JUN 21 1995  
4-7