

15-167-21,903-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SW SEC. 10, T 14S, R 13W

1650 FEET FROM ~~NS~~ SECTION LINE

1650 FEET FROM ~~W~~ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6343

LEASE NAME Dumler E WELL # 1

OPERATOR: Host Oil Operations
NAME & ADDRESS Box 811, Russell, Ks. 67665

COUNTY Russell

WELL TOTAL DEPTH 2475 80.44 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8" FEET 232

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR H + H Casing Pulling LICENSE NUMBER 6053

ADDRESS Box 563, Burton, Ks. 67020

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 11 MONTH: 8 YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Don Hurst

(COMPANY NAME) H + H Casing Pulling (PHONE) 716-663-8881

WERE: Order 165 lbs. 50 pos mix - 4 3/4 gal. - 3 9/16 gal. oil, 15 lbs. gel., 5 lbs. hulls & 8 5/8" plug.

PLUGGING PROPOSAL RECEIVED BY [Signature]
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 5:15 PM DAY: 11 MONTH: 8 YEAR: 19 83

ACTUAL PLUGGING REPORT 8 5/8" - 232' 4 1/2" set at 2474' w/ 125 lbs.

Top perf. 2387', Plug Bottom w/ 4 lbs cement, sand & 4 lbs. cement to 2330'. Shot pipe 2 times & recovered 1745'. Pumped in 8 5/8", 4 lbs hulls, 12 lbs gel., 65 lbs cement, 3 lbs gel., 1 lb. hulls, released plug & followed w/ 100 lbs. cement w/ 500 pounds pressure.

REMARKS: By Allied Cementing Co. Inc.

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1983
08-15-83
CONSERVATION DIVISION
Wichita, Kansas

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

SIGNED [Signature] ✓
(TECHNICIAN)

INVOICED
DATE 8-18-83
INV. NO. 5240-W

FORM CP-2/3
REV. 6-83