

6-30

4-060409

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-167-20,109-00-00

NW NW NE /4 SEC. 27, 14 S, 12 W  
4950 feet from S section line  
2310 feet from E section line

Operator license# 5184 Lease Keough well # 2

Operator: Shields Oil Producers, Inc. County Russell

Address: Shields Building Well total depth 3182 feet <sup>103.41</sup>  
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 592 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 11:00A.M. Day: 30 Month: June Year: 93

Plugging proposal received from: Darrell Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 200 sx. 60/40 posmix - 10% gel. - hulls.  
Plug through casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 2:00P.M., Day: 30, Month: June, Year: 93

Actual plugging report: 8 5/8" to 592'. 5 1/2" to 2975'. Sand back to  
2800' and spot 5 sx. cement with dump bailer. Shots at 2600' - 2400' -  
2200' - 2000'. Recovered 2000' of casing. Pulled casing to 1250'.  
Mixed 35 sx. cement with 100# hulls and displaced plug to 1200'.  
Pulled casing to 600'. Mixed 50 sx. cement with 100# hulls and  
displaced to 500'. Pulled casing to 300' and circulated cement to  
surface with 75 sx. cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES     X NO    

Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO    

Plugged through TUBING    , CASING X. Elevation: 1681

I did X did not     observe the plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
07-14-1993  
JUL 14 1993

(agent)  
CONSERVATION DIVISION  
Wichita Kansas

Form CP-2/3

7-16-93  
38125