

6 061699

10-26

API NUMBER 15-1167-20045-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW, SEC. 27, T. 14 S, R. 12 W/E  
4950 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Morris Well # 3

Operator: Graham Michaelis Corp

County Russell 102.90

Name & Address Box 247

Well Total Depth 3166 feet

Wichita, Ks. 67201

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00AM Day: 26 Month: Oct Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) \_\_\_\_\_

were: Order 200 sks 60/40 Poz 6% Gel 3% Cal Cl 5 sks Hulls.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 21 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 26 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 317' w/185 sks. 5 1/2" set at 3151' w/150 sks.

Top perf at 2818'. Plugged bottom w/sand and 5 sks cement to 2750'. Shot pipe three times and recovered 2200'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 175 sks cement w/ psi. Ran line to 1000'.

Remarks: By Allied  
(If additional description is necessary, use BACK of this form.)

~~INVOICE~~ INVOICE Do not observe this plugging.

Signed Gilbert G. Scheck  
(TECHNICIAN)  
Gilbert G. Scheck

DATE 11-29-88

INV. NO. 23144