

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-167-21050-00-00 (of this well)

Operator's Full Name Corie Oil Co.

Complete Address Box 534, Russell, Kansas 67665

Lease Name Cook Well No. 1

Location NE NW NE Sec. 26 Twp. 14 Rge. 11 (E) (W) X

County Russell Total Depth 3263'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A ~~_____~~

Other well as hereafter indicated _____

Plugging Contractor Kelse Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:30 PM Day 21 Month 12 Year 1977

The above well was plugged as follows:

Sanded Back to 2200' and 4 sx cement with dump Bailer.
Squeezed thru 8 5/8" surface casing with 3 sx hulls,
15 sx mud gel, 1 sx hulls, plug, and 100 sx cement.
Max. pres. 700#. Shut in pres. 300#.
Plug Back T.D. 2262'. Top perf. at 2224'.
Recovered 1313' of 4 1/2" casing.
3262' of 4 1/2" casing cemented with 125 sx cement.

217' of 8 5/8" surface casing cement circ.
I hereby certify that the above well was plugged as herein stated.

RECORDED

Signed: [Signature]
Well Plugging Supervisor

12-29-77
6475-5N