

15-167-20464-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD


Russell County, Sec. 25 Twp. 14 Rge. 11 (E) (W) X
NW NW NW

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Will P. Ash
Lease Name Beisel Well No. 2
Office Address 360 Sutton Place
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-1-71 _____ 19____
Plugging completed 6-5-71 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2924 Feet

Show thickness and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	269 1/2	None
				4 1/2"	2922	2288.26'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed a plug to 2850'. Dumped 20 gallons sand and 4 sacks cement.
Shot casing at 2320'. Laid down a total of 73 joints of 4 1/2" casing.
Added squeezed well with 15 sacks gel and 90 sacks pozmix with 4% gel at 400 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Co. Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 22nd day of June, 19 71
Elaine H. Taylor
Notary Public.
My commission expires December 14, 1973



DRILLERS LOG

BEISEL NO. 2


CASING RECORD:	OPERATOR: Will P. Ash	DESCRIPTION:
8-5/8" @ 269½' w/190 sax cement	CONTRACTOR: Sage Drilling Co.	NW NW NW Sec. 25-14S-11W Russell Co., Kansas
TOTAL DEPTH: 2924'	COMMENCED: March 24, 1971	ELEVATION: 1671KB
	COMPLETED: March 30, 1971	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	100	
Red Bed & Shale	100	272	
Red Bed	272	519	
Anhydrite	519	547	
Shale & Shells	547	575	
Shale	575	1228	
Shale & Lime	1228	2335	
Lime	2335	2484	
Lime & Shale	2484	2640	
Lime	2640	2727	
Lime & Shale	2727	2870	4½" @ 2923'
Lime	2870	2924	w/100 sax cement

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 2nd day of April, 1971.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1971
CONSERVATION DIVISION
Wichita, Kansas