

15-167-20513-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Russell County, Sec. 25 Twp. 14S Rge. (E) 11W (W)

Location as "NE/CNW&SW&" or footage from lines Ap NE NW NW
Lease Owner Will P. Ash
Lease Name Beisel Well No. 3
Office Address
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 4, 1972
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced March 4, 1972
Plugging completed March 4, 1972
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Don Truan of Russell)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 2869 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	262'	8-5/8"	262'	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 480 Feet,
plug and 40 sax Cement; Mud to 250 Feet,
plug and 25 sax Cement; Mud to 40 Feet,
1/2 sax Halls, Solid Plug & 10 sax Cement
to Base of Cellar; 2 sax Cement in Rat Hole.
Job completed @ 6:00 A.M.

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1972
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sun Oilwell Cementing Co.
Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described

well, being first, duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 6th day of March 1972
November 26, 1974
My commission expires
Louise K. Whitted - Notary Public



15-167-20513-00-00

DRILLERS LOG

BEISEL NO. 3

CASING RECORD:	OPERATOR: Will P. Ash	DESCRIPTION:
8-5/8" @ 262' w/180 sax cement	CONTRACTOR: Sage Drilling Co.	Ap. NE NW NW Sec. 25-14S-11W Russell Co., Kansas
TOTAL DEPTH: 2869'	COMMENCED: February 28, 1972	ELEVATION: 1680KB
	COMPLETED: March 4, 1972	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Top Soil, Sand & Shale	0	265	
Red Bed, Sand & Shale	265	425	
Red Bed	425	534	
Anhydrite	534	562	
Red Bed, Shale & Lime	562	1425	
Shale & Lime	1425	1870	
Lime & Shale	1870	2423	
Shale & Lime	2423	2478	
Lime & Shale	2478	2869	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 6th day of March, 1972.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1972
CONSERVATION DIVISION
Wichita, Kansas