

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-167-21672-00-00

LEASE NAME G. Small

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
CN/2 N/2 SE/4

SEC. 22 TWP. 14S RGE. 11W (E) or (W)

COUNTY Russell

Date Well Completed

Plugging Commenced 4-23-87

Plugging Completed 5-11-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L.G. Stevenson & Co., Inc.

ADDRESS 1524 North 143 Street E.
Wichita, Kansas 67230

PHONE # (316) 733-2465 OPERATORS LICENSE NO. 5462

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 2890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	252.23'	none
				4-1/2"	2279'	1631'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 2225' and 4 sacks cement. Shot pipe @1737',
1631', pulled a total of 40 joints of 4-1/2" casing. Plugged surface with 5 hulls,
and 100 sacks econolite.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347
Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 347
Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 14th day of May

Irene Hoover
Notary Public
STATE CORPORATION COMMISSION
RECEIVED
MAY 18 1987

My Commission Expires:




CONSERVATION VCR-4
Revised 07-86

CASING RECORD: COMPANY: L. G. Stephenson & Co., Inc. DESCRIPTION:
 8 5/8" @ 252.23' CONTRACTOR: Red Tiger Drilling Company C N/2 N/2 SE/4
 w/175 sx cement COMMENCED: May 7, 1981 Sec. 22-T14S-R11W
 Russell County, Kansas
 4 1/2" @ 2,279' COMPLETED: May 14, 1981
 w/125 sx cement TOTAL DEPTH: 2,890' ELEVATION: 1,659' KB


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Sand, Hard Sand & Shale	0	200	
Shale	200	256	
Shale & Hard Sand	256	348	
Red Bed & Shale	348	487	
Anhydrite	487	518	
Shale	518	1182	
Lime & Shale	1182	2450	
Lime	2450	2890	
RTD		2890	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

 Gloria Fawcett

Subscribed and sworn to before me this 19th day of May, 1981.




 Notary Public