

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado DePue Bldg  
 Wichita, Kansas 67202

15-051-01641-00-01  
 WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-051-01641-0001

RECEIVED  
 JAN 31 1989  
 01-31-89  
 CONSERVATION DIVISION  
 Wichita, Kansas

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

API NUMBER DRILLED IN 1956  
 LEASE NAME CAVE  
 WELL NUMBER FOUR (4)  
2310 Ft. from S Section Line  
3300 Ft. from E Section Line  
 SEC. 8 TWP. 11S RGE. 18 ~~XXXX~~ (W)  
 COUNTY ELLIS  
 Date Well Completed 1956  
 Plugging Commenced 11-9-88  
 Plugging Completed 11-9-88

LEASE OPERATOR L-K WIRELINE, INC.

ADDRESS P.O. BOX 1188--HAYS, KS 67601

PHONE# (913) 625-6877 OPERATORS LICENSE NO. 5453

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JUNE 1988 (date)

by DON BUTCHER (KCC District Agent's Name).

Is ACO-1 filed? UNKNOWN If not, is well log attached? WAS ATTACHED TO PLUGGING APPLICATION

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3557

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	212	NONE
				5-1/2	3585	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

PUMPED IN 5 1/2" CASING, 125 SX CEMENT WITH 1/4# FLOCELE. MAXIMUM 400#, SHUT IN @ 300# PSI.  
PUMPED IN 8-5/8" CASING, 25 SX CEMENT, MAX 500#.  
PERMANENT PLUG WAS SET @ 3100', ANHYDRITE WAS PERFORATED @ 1320', WELL WAS SQUEEZED @ 530'  
 (If additional description is necessary, use BACK of this form.) AND 764'

Name of Plugging Contractor B-J TITAN SERVICES License No. \_\_\_\_\_

Address P.O. BOX 69--HAYS, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L-K WIRELINE, INC.

STATE OF KANSAS COUNTY OF ELLIS, ss.

BILL R. LONGPINE, PRESIDENT, L-K WIRELINE, INC. (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill R. Longpine

BILL R. LONGPINE, PRESIDENT

(Address) P.O. BOX 1188--HAYS, KS 67601

SUBSCRIBED AND SWORN TO before me this 30TH day of JANUARY, 19 89

Colleen Payton  
 NOTARY PUBLIC  
 State of Kansas  
 My Comm. Expires: MAY 2, 1991

COLLEEN PAYTON Notary Public