

15-167-20980-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Russell County. Sec. 18 Twp. 14 Rge. 12 E/W  
Location as "NE/CNW/SW" or footage from lines  
NE NE NE

Lease Owner Mai Operations  
Lease Name Albert Well No. 1  
Office Address P. O. Box 33, Russell, Kansas 67665  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed November 10 19 76  
Application for plugging filed November 10 19 76  
Application for plugging approved November 10 19 76  
Plugging commenced November 10 19 76  
Plugging completed November 10 19 76  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2997  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug @ 480' w/40 sacks cement thru drill pipe.  
Middle plug at 240' w/20 sacks cement thru drill pipe.  
Top plug at 40' w/1/2 sack hulls and 10 sacks cement  
2 sacks cement in rat hole.

*11-10-1976*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Leonard Williamson (employee of owner) or (owner/operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson  
Box 823, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1976

deced by M. Hague  
Notary Public.

My commission expires April 11, 1978

DRILLERS WELL LOG

15-167-20980-00-00

DATE COMMENCED: November 4, 1976  
 DATE COMPLETED: November 10, 1976

Mai Operations  
 ALBERT # 1  
 NE NE NE  
 Sec 18-T14S-R12W  
 Russell County, Kansas

ELEVATION: 1794 K.B.

0 - 36'	Surface Soil, Shale, Post Rock
36 - 254'	Post Rock, Clay, Sand Streaks
254 - 460'	Sand, Shale, Shells
460 - 723'	Red Bed, Shale
723 - 760'	Anhydrite
760 - 1389'	Red Bed, Shale, Shells
1389 - 1515'	Lime and Shale
1515 - 1815'	Shale, Lime, Shells
1815 - 2330'	Lime, Shale
2330 - 2340'	Lime
2340 - 2420'	Lime, Shale, Sand
2420 - 2640'	Lime, Shale
2640 - 2873'	Lime
2873 - 2877'	Shale
2877 - 2904'	Lime
2904 - 2946'	Shale
2946 - 2997'	Lime
2997'	RTD

FORMATION TOPS

Anhydrite	723
Topeka	2640
Heebner	2873
Toronto	2890
Douglas	2904
Kansas City	2946
RTD	2997

SURFACE PIPE:

Set used 2 3/4", 8 5/8" pipe  
 at 253' w/150 sacks Common,  
 2% Gel, 3% cc.

11-16-1976

AFFIDAVIT

STATE OF KANSAS }  
 COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 12th day of November, 1976.

Martha M. Hayes  
 Notary Public

My Commission Expires: April 11, 1978