

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-20,109-00-00

LEASE NAME Keough

WELL NUMBER #2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330' Ft. from N Section Line
2310

Ft. from E Section Line
NW NW NE

SEC. 27 TWP. 14 RGE. 12W (E) or (W)

COUNTY Russell

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg. Russell, Kansas 67665

PHONE # (913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 6-25-93

Plugging Completed 6-30-93

The plugging proposal was approved on _____ (date)

by Hubert Deines (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3182'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	592'	none
				5-1/2"	2975'	2005'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ foot to _____ foot each set.

Plugged off bottom with sand to 2790' and 5 sacks cement. Shot pipe @2531', 2407', 2219', 2005', pulled to 1250', pumped 50 sacks cement w/100# hulls, pulled to 600', pumped 50 sacks cement w/100# hulls, pulled to 300', pumped 75 sacks cement w/100# hulls and circulated to surface. 60/40 pos. 10% gel. Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 93

Jane Herzberg
Notary Public

My Commission Expires: 

RECEIVED
STATE CORPORATION COMMISSION
07-09-1993
JHM
Revised 09-1993
CONSERVATION DIVISION
Wichita, Kansas




Shields

WELL LOG

15-167-20109-00-00 ^{Russell, Kansas}

Operator: Shields Oil Producers, Inc.
 Well: Keough #2
 Commenced: 9-4-67
 Completed: 9-15-67
 Contractor: Shields Drlg., Co.

Well Description: NW NW NE



Sec. 27-14S-12W
 Russell Co., KS

CASING RECORD

Size	Run	Pulled
8 5/8	592'	Cement w/300 sks
5 1/2	2975'	Cement w/75 sks

Elevation: 1681 K.B.

Treatment: 2750 gal

Production: 25 BOPD + 25 BWPD

Tops: Anhydrite 588'

Heebner 2740'

Toronto 2760'

L-KC 2825'

..... Figures Indicate Bottom of Formations

Sand, post rock, clay & shale	130'
Shale & sand	400'
Shale, shells & redbed	588'
Anhydrite	620'
Shale	745'
Shale, shells & salt	1,250'
Shale & lime	1,570'
Lime	1,820'
Lime & shale	2,520'
Lime	3,182' RTD

RECEIVED
STATE OPERATIONAL COMMISSION

MAR 4 1993
03-04-1993
CONSERVATION DIVISION
Wichita, Kansas