

15-167-22123-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Russell SEC. 27 TWP. 14 RGE. 12 ~~EA~~
Location as in quarters or footage from lines:
NW NE SW

Lease Owner Southern States Oil Company
Lease Name Miller "A" Well No. 1
Office Address P.O. Box 1365, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed June 13, 1983
Application for plugging filed June 13, 1983
Plugging commenced June 13, 1983
Plugging completed June 13, 1983
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation _____ Depth to top _____ bottom _____ T.D. 3174'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

- 1st Plug @ 3160' w/20 sx.
- 2nd Plug @ 570' w/80 sx.
- 3rd Plug @ 300' w/40 sx.
- 4th Plug @ 40' w/10 sx.
- 5th Plug @ Rathole w/10 sx.
- 6th Plug @ M.H. w/10 sx.
- Plug down 10:45 AM., June 13, 1983
- Plugged with 170 sx. 50/50 Pozmix

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


K.T. Woodman (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) K.T. Woodman
1008 Douglas Building, Wichita, KS
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 83

My Commission expires: April 20, 1985

Kathryn A. Voigt
RECEIVED
Kathryn A. Voigt Notary Public.
STATE CORPORATION COMMISSION



JUN 24 1983
06-24-1983
CONSERVATION DIVISION
Wichita, Kansas

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

15-167-22123-00-00

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

*Rec'd
06-24-1983*

June 20, 1983

Company:	Southern States Oil Company
Farm:	Miller "A" #1
Location:	NW NE SW
Section:	27-14S-12W
County:	Russell
Contractor:	Woodman & Iannitti Drilling Company
Total Depth:	3174'
Comm:	June 8, 1983
Comp:	June 13, 1983
Casing:	8-5/8" 24# set @ 257' w/165 sx. Common 3% CC, 2% Gel

Figures Indicate Bottom Formations:

35	Shale
70	Post Rock
258	Shale & Sand Streaks
572	Shale & Red Bed
600	Anhydrite
666	Shale
1318	Shale
1665	Shale
1985	Shale
2275	Lime & Shale
2555	Lime & Shale
2755	Shale & Lime
2895	Lime & Shale
2916	Lime
2970	Lime
3070	Lime
3155	Lime
3174	Lime

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K. T. Woodman
K.T. Woodman, Partner