

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#4

API NUMBER 15-167-20045-00-00

LEASE NAME Morris

WELL NUMBER #3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 14 RGE. 12W (E) or (W)

COUNTY Russell

Date Well Completed

Plugging Commenced 10/20/88

Plugging Completed 10/26/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Graham-Michaelis Corporation

ADDRESS P.O. Box 247
Wichita, KS 67201

PHONE#(316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3166'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	317	none
				5 1/2	3151	2125

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom with sand to 2750', ran 5 sacks cement, shot @2302', 2125',
plugged surface with 500# hulls, 200 sacks 60/40 pos 6 1/2 gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-michaelis Corporation

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and I believe that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS67524

SUBSCRIBED AND SWORN TO before me this 1st day of Novemver, 1988

Notary Public

My Commission Expires:



15-167-20045-00-00

WELL LOG

Bennett & Roberts Oil Operations
Box 633
Russell, Kansas

MORRIS #3
NE NE NW Sec. 27-14S-12W
Russell County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 5-9-67
Completed: 5-16-67

Casing Record: 8-5/8" @ 317' w/185 sacks Sunset, 2% Gel
5-1/2" @ 3151' w/150 sacks 60-40 Pozmix, 2% Gel

<u>FORMATION TOPS</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & Shale	0	50	1676 Gr.
Shale	50	319	1678 D.F.
Shale (Red Bed)	319	575	1681 K.B.
Anhydrite	575	608	
Shale	608	995	
Shale & Shells	995	1270	
Shale & Lime	1270	2496	
Lime	2496	2732	
Lime & Shale	2732	2818	
Lime	2818	3105	
Conglomerate	3105	3166	
Total Depth	3166		

<u>FORMATION TOPS</u>		
Anhydrite	575	+1106
Topeka	2496	- 815
Heebner	2732	-1051
Toronto	2753	-1072
Lansing	2818	-1137
Conglomerate	3105	-1424
Total Depth	3166	-1485

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NE NW Section 27-14S-12W, Russell County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 19th day of May, 1967.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: December 12, 1970.

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1988
09-22-1988
CONSERVATION DIVISION
Wichita, Kansas