

15-167-00229-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD ^{OCT 16 1950}

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

SE NE Se Russell County. Sec. 26 Twp. 14 Rge. 12 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SE
Lease Owner National Associated Pet Co
Lease Name Bachman Well No. 1.
Office Address Suite 502, Ritz Bldg Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.
Date well completed 10-17-50 19
Application for plugging filed 10-17-50 19
Application for plugging approved 10-17-50 19
Plugging commenced 10-17-50 19
Plugging completed 10-17-50 19
Reason for abandonment of well or producing formation Dry Hole.
If a producing well is abandoned, date of last production Dry Hole. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Petty.
Producing formation Depth to top Bottom Total Depth of Well 3200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
					231 Feet 8 5/8	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.
~~Hole fixed~~ Hole filled with rotary mud to 231 feet, plug set, 15 sacks of cement on top, Rotary mud on top of cement, plug set at 40 feet, 10sacks of cement on top, surface pipe cut off at bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1950
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to National Associated Pet Co
Address Suite 502, Ritz Bldg, Tulsa, Oklahoma.

STATE OF Kansas, COUNTY OF Barton, ss.
O. C. Arnott (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) *O. C. Arnott*

SUBSCRIBED AND SWORN to before me this 17th day of October, 19 50.
April 16, 1951
My commission expires.....
Altha L. Fishman
Notary Public.

22-5133-s 9-48-10M
PLUGGING
FILE SEC-26 T 14 R 20
BOOK PAGE-37 LINE X

CERTIFIED DRILLERS LOG

15-167-00229-00-00

Company: National Associated Petroleum Company Lease: Bachman #1
 Contractor: H & H Drilling Company Location: SE NE SE
 Commenced: 10-4-50 26-14-12W
 Completed: 10-17-50 Russell County
 Elevation: D&A 1692 D.F. Kansas
 Casing Record:
 2 1/2" 8-5/8" cas. 11/175 cas.

Formation	Depth	Remarks
Sand	0-40	
Red Bed	40-221	
Shale	221-266	
Red Bed	266-282	SLM & Slope Test Ok - 500'
Anhydrite	282-284	
Red Bed	284-705	
Shale & Shell	705-1000	SLM & Slope Test Ok - 1000'
Sand	1000-1150	
Salt	1150-1180	
Sand & Shale	1180-1241	1/2 Trip 1241
Shale & Lime	1241-1469	1/2 Trip
Shale & Lime	1469-1647	SLM & Slope Test Ok
Lime	1647-1784	
Lime & Shale	1784-1968	Trip @ 1780
Lime & Shale	1968-2150	Circ. @ 2110' 45 mins. Circ. @ 2150
Lime & Shale	2150-2206	20 mins. SLM & Slope Test Ok
Lime & Shale	2206-2400	
Lime & Shale	2400-2506	1/2 Trip
Lime & Shale	2506-2546	1/2 Trip SLM Ok
Lime & Shale	2546-2625	
Lime	2625-2700	
Lime	2700-2716	Trip
Lime	2716-2726	1/2 Trip
Lime & Shale	2726-2826	SLM Ok
Lime & Shale	2826-2900	Circ. @ 2826 1 hr. 10 mins. Circ. 2900
Lime	2900-2930	1 hr. 45 mins. Circ. @ 2900 - 60 mins.
Lime & Shale	2930-2943	Circ. @ 2930 - 55 mins. Trip @ 2930
Lime & Shale	2943-3000	Circ. @ 2991 - 35 mins.
Lime	3000-3054	Circ. @ 3023 - 60 mins.
Lime & Shale	3054-3128	
Lime & Shale	3128-3136	
Conglomerate	3136-3150	Circ. @ 3136 - 1 hr. 35 mins.
Lime	3150-3200	Trip - Circ. @ 3200 - 60 mins.
Total Depth	3250	Circ.

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

R. E. Hartman

RECEIVED
 STATE CORPORATION COMMISSION
 10-21-1950
 OCT 21 1950
 CONSERVATION DIVISION
 - MICHAEL, KANAS

STATE OF KANSAS }
 COUNTY OF SEDGWICK }

Subscribed and sworn to before me this 20th day of October 1950.

George L. Laird

MY COMMISSION EXPIRES MAY 13, 1953

PLUGGING
 FILE SEC 26 T 14 R 20
 BOOK PAGE 37 LINE 2