

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED
12-11-2002
DEC 11 2002

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 15-167-22,205 - 00-00
LEASE NAME Pasek
WELL NUMBER 1
990 ft. from S Section Line
990 ft. from E Section Line
SEC. 16 TWP. 14 RGE. 12 (E) or (W)
COUNTY Russell

LEASE OPERATOR GLM Company
ADDRESS PO Box 193, Russell, KS 67665
PHONE # (785) 483-2123 OPERATORS LICENSE NO. 3134
Character of well oil

Date Well Completed _____
Plugging Commenced 11/27/02
Plugging Completed 11/29/02

(Oil, Gas, D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 11/27/02 (date)
by Herb Deines (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3340

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	406	none
				5 1/2	3339	1650

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand bottom, bail 5 sks cem. Shot pipe at 2250, 2050, 1850, 1650, work free. Pull to 1350, pump 90 sks cem. w/1 sack hulls. Pull to 650, pump 30 sks cem. w/1 sack hulls. Pull to 200, circulate to surface w/40 sks cem. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GLM Company

STATE OF KANSAS COUNTY OF RICE, ss.


RICHARD MCINTYRE (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 401 W. MAIN LYONS KS 67554

SUBSCRIBED AND SWORN TO before me 9th day of DEC, 2002

[Signature]
Notary Public

My commission Expires: 2-15-03



OP