

API NUMBER 15-167-22,241-00-00

LEASE NAME Tepe

WELL NUMBER B2

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 16 TWP. 14 RGE. 12 ~~W~~ or (W)

COUNTY Russell

Date Well Completed _____

Plugging Commenced 9/3/91

Plugging Completed 9/3/91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Bennett & Schulte Oil Company

ADDRESS Box 329 Russell, KS 67665

PHONE# (913) 483-2721 OPERATORS LICENSE NO. 6246

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 3, 1991 (date)

by Marion J. Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 3265

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
		0	611	8 5/8"	611	None
		0	3264	5 1/2"	3264	1438'

10-31-1991
 OCT 31 1991
 STATE CORPORATION COMMISSION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ordered 225 sx. 65/35 pozmix - 8% gel. - 5 sx. hulls. Pumped in 8 5/8" surface pipe with 15 sx. cement followed with 210 sx. cement with 1 sx. hulls. Maximum pressure 600 p.s.i. Shut in at 400 p.s.i. Cemented by Allied Cementing, Russell, Kansas.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Super Oilwell Service License No. 6535

Address West Wichita Ave. Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bennett & Schulte Oil Company

STATE OF Kansas COUNTY OF Russell, ss.


Frank R. Schulte Partner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank R. Schulte Partner

(Address) Box 329 Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 25th day of October, 19 91

My Commission



Ralph L. Schulte
 Notary Public

well Log Available

TeppeB # 2 15-167-22241-2

FORMATION TOPS
(Wire-Tech, Radiation Guard Log)

16-14-12

SE SE SE

<u>FORMATION</u>	<u>DEPTH</u>	<u>MINUS DATUMS</u>
Anhydrite	608	+1108
Base-Anhydrite	639	+1077
Grand Haven	2177	-461
Dover	2203	-437
Tarkio Lime	2254	-538
Elomont	2311	-595
Topeka	2527	-811
Heebner	2762	-1046
Toronto	2781	-1065
Douglas	2799	-1083
Lansing-Kansas City	2847	-1131
Base-Kansas City	3115	-1399
Conglomerate	3172	-1456
Arbuckle	3193	-1477
Rotary Total Depth	3265	-1549
Log Total Depth	3258	-1542

Lithology: Zones of Interest

NOTE: No shows were logged in the Tarkio or Topeka sections.

Topeka 2527-Top (-811)

Heebner 2762 (-1046)

Toronto 2781-Top (-1065)
3182-84

LS: White to light gray, fine crystalline and dense. Trace of spotty stain and chert. No free oil or odor.

RECEIVED
STATE CORP. AND COMMISSION

08-16-1991
AUG 16 1991

CONSERVATION DIVISION
Wichita, Kansas