


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Russell County, Sec. 14 Twp. 14 Rge. 12 (E) W (W)
Location as "NE/CNW&SW" or footage from lines SW SW SW
Lease Owner Morgenstern & Specter, Inc.
Lease Name Walter Well No. 2
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 4-21-62 19
Application for plugging filed 12-15-64 19
Application for plugging approved 12-16-64 19
Plugging commenced 12-20-64 19
Plugging completed 12-22-64 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truman
Producing formation arbuckle Depth to top 3205' Bottom 3229' Total Depth of Well 3230' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	213'	None
				XXXX	XXXX	
				4-1/2"	3229'	2732'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3230', sanded hole to 3200' and dumped 4 sacks of cement @ 3200' with dump bailer. Pulled 4 1/2" casing to 300' and circulated with 6 sacks of gel mud. Pulled 4 1/2" casing to 200' and pumped 25 sacks of cement. Pulled balance of 4 1/2" casing, checked fluid to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1965
01-04-1965
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner of property) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 1964

My commission expires May 20, 1968 Milton J. Willis Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-167-19391-00-00

Company- SHELLEY-MILLER DRILLING CO.
Farm- Walter No. 2

SEC. 14 T. 14 R. 12W
SW SW SW

Total Depth. 3230'
Comm. 4-12-62 Comp. 4-21-62
Shot or Treated.
Contractor.
Issued. 9-15-62

County Russell
KANSAS



CASING:
8 5/8" 213' cem w/135 ex.
4 1/2" 3229' cem w/100 ex.

Elevation. 1742' RR

Production. 45 BOPD, NW

Figures indicate Bottom of Formations.

surface	10
shale	160
sand	180
shale & shells	215
shale, shells & sand	375
shale & shells	585
shale & red bed	600
Anhydrite	635
shale & shells	1270
lime & shale	1470
lime sandy	1570
lime & shale	1750
lime, shale & sand	1920
shale & lime	2645
lime & shale	2815
lime	3129
lime & shale	3195
lime	3205
Arbuckle	3220
lime	3230 RTD
Total Depth	

TOPS: LOG	
Huebner	2778
Toronto	2798
Douglas	2813
Lansing	2862
Conglomerate	3185
Arbuckle	3205

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1965
04-27-1965
CONSERVATION DIVISION
Wichita, Kansas