

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15167-00269-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Russell County, Sec. 13 Twp. 14 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines Center S 1/4  
Lease Owner Advance Drilling Co.  
Lease Name Herhel Well No. 1  
Office Address Box 44, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-6 19 57  
Application for plugging filed 5-4 19 57  
Application for plugging approved 5-4 19 57  
Plugging commenced 5-5 19 57  
Plugging completed 5-6 19 57  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt  
Producing formation FT. Riley Lime Depth to top 1518 Bottom 1552 Total Depth of Well 1593 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand	Water	15	32	10"	53'	53'
Sand	Water	85	98	8 5/8"	372'	372'
Sand	Water	190	240	7"	646'	646'
Sand	Water	320	330			
Sand	Water	340	350			
Sand	Water	590	616			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud by Halliburton - Pulled 7" casing started 8" casing - pulled up to 275' - Set bridge 300' up to 275' using plug and crushed rock. Run 275' tubing on top of bridge; pulled 8" casing then cemented thru' tubing on top of bridge with 50 sax cement by Halliburton. Pulled 10" casing set bridge at 30' using plug and crushed rock cemented to base of cellar with 16 sax cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Advance Drilling Co.  
Address Box 44, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Bernard R. Gleason (employee of/owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bernard R. Gleason  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9<sup>th</sup> day of May, 1957

Mary Ann Lee Notary Public.

My commission expires March 25, 1961

PLUGGING  
FILE SEC 13 T 14 R 12W  
BOOK PAGE 11 LINE 41

CON: 05-10-1957

15-1107-00269-00-00

Advance Drilling Company  
Russell, Kansas

Herbel Lease

Well No. 1

Location: Center SW  $\frac{1}{4}$  13-14-127 Russell County, Kansas

Date Started: 4-16-57

Date Completed: 4-25-57

Casing Record:

10" 53'  
8 5/8" 372'  
7" 646'

FORMATION RECORD: Figures Indicate Bottom of Formation

Cellar	6	Shale	1000
Clay	15	Salt	1250
Sand	32	Shale	1270
Shale	85	Lime	1320
Sand	98	Shale	1340
Shale	110	Lime	1390
Red Rock	125	Red Rock	1390
Shale	160	Shale	1415
Red Rock	190	Lime	1430
Sand	240	Shale	1453
Shale	320	Lime	1488
Sand	330	Shale	1495
Shale	340	Red Rock	1512
Sand	350	Shale	1518
Shale	367	Lime (Ft. Riley)	1552
Red Rock	590	Shale	1557
Sand	616	Lime	1593
Red Rock	780		
Shale	818	TOTAL DEPTH	1593
Red Rock	880	Dry Hole	
		Plugged 5-6-57	

WATER RECORD

Sand	15 - 32	Water
Sand	85 - 98	Water
Sand	190 - 240	H.F.W.
Sand	320 - 330	H.F.W.
Sand	340 - 350	H.F.W.
Sand	590 - 616	H.F.W.

APR 26 1957

05-10-1957

PLUGGING	
FILE SEC	13 T. 14 R. 12W
BOOK PAGE	11 LINE 41