

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 10 1969 01-10-69
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Mason of Dunne - Gardner has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Inc.

Complete Address: 1101 Wichita Plaza Wichita, Ks.

Lease Name: Schulte Well No. 1

Location: NW SW NE Sec. 1 Twp. 14 Rge. 16 (E)(W) XX

County: Ellis Total Depth 3420' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Mason was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 450' and displace
50 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

J. O. Mason
 Conservation Division Agent