

State of Kansas



15-051-30259-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

APR 27 1960
Conservation Division

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Rodie of Rains & Williamson has this date requested permission to plug the following described well:

Mr. Rodie guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 1425 Wichita Plaza, Wichita, Kans.

Lease Name: Younger Well No. 1

Location: SE-SW-NE Sec. 6 Twp. 14 Rge. 17 (E) (W) X

County Ellis Total Depth 7621 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rodie was instructed to plug the well as follows:
Jett pits circulated hole with heavy mud, set cementing plug at 540 ft.,
and displace 20 sac cement thru drill pipe, heavy mud to 215 ft., set
cementing plug and displace 20 sac cement thru drill pipe, heavy mud
to 40 ft., set cementing plug, 1/2 sac hulls and 10 sac cement, cementing
to base of callar. Plug rat hole with two sac cement.

Very truly yours,

Geo Massey
Conservation Division Agent