

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dobbs of Duke Drlg. has this

date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: Al Tipton

Complete Address: Box 157, Hays, Ks.

Lease Name: Younger "T" Well No. 1

Location: NW SE NE Sec. 6 Twp. 14 Rge. (E)(W) 17

County: Ellis Total Depth 3580' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe. Heavy mud to 215' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Geo Messing
Conservation Division Agent