



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Robert Herren of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. John P. Jennings guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corp.

Complete Address: 1000 Century Plaza, Wichita, Kansas 67202

Lease Name: Dietz Well No. # 1

Location: NE SW SW Sec. 12 Twp. 14 Rge. 13 (E)(W) W

County: Russell Total Depth 3360 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Robert Herren was instructed to plug the well as follows:

8 5/8" csg. 250' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 240' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Sun Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don L. Small
Conservation Division Agent