

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Russell County, Sec. 14 Twp. 14 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Duke & Wood Drilling Company

Lease Name Jones 'C' Well No. 1

Office Address Box 123, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 9 19 53

Application for plugging filed January 4 19 54

Application for plugging approved January 7 19 54

Plugging commenced January 25 19 54

Plugging completed January 26 19 54

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Warren H. Horner

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2380 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 248' | None |
| | | | | 5 1/2" | 2380' | 1678.75' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 2322 ft. with crushed rock, dumped 5 sacks
cement. Mudded back to 210 ft, put in 5 ft. rock bridge. Mixed and
dumped 20 sacks cement. Mudded hole back to 35 ft., put in 5 ft. rock
bridge. Mixed and dumped 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company

Address Box 304, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Cecil M. Olson (employee of owner) or (~~CONDUCTOR~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M Olson


Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of February, 19 54

Dean T. Doolan
Notary Public.

My commission expires April 29, 1957

02-10-54



15-167-00070-00-00

Jones C #1
WELL LOG
SW SW SW of 14-14-13W
Russell County, Kansas

Started: November 3, 1953
Completed: November 9, 1953

Elevation 1819 KB
Anhydrite 758 (-1061)
Tarkio (1st) 2338 (- 519)
Tarkio (2nd) 2357 (- 538)

| | |
|-----------|--------------------------------|
| 0-30 | Surface clay |
| 30-120 | Gravel, clay and sand |
| 120-190 | Clay, shale, coal and sand |
| 190-220 | Shale, coal and clay |
| 220-300 | Shale |
| 300-480 | Shale, clay and sand |
| 480-758 | Red bed |
| 758-794 | Anhydrite |
| 794-1100 | Shale and shells |
| 1100-1325 | Salt and shells |
| 1325-1640 | Shale and shells |
| 1640-1695 | Shale, shells and lime streaks |
| 1695-1905 | Lime and shale |
| 1905-2155 | Lime and shale |
| 2155-2338 | Lime and shale |
| 2338-2346 | Shale and sand |
| 2346-2357 | Lime and shale |
| 2357-2365 | Shale and sand |
| 2365-2380 | Lime and shale |
| 2380 | TOTAL ROTARY DEPTH |

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton, SS

I, Lynn O. Duke, of the DUKE & WOOD DRILLING COMPANY being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Lynn O. Duke
Partner

Subscribed and sworn to before me this 10th day of December 1953.

Dean T. Looley
Notary Public

My commission expires: April 29, 1957.

