

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas


OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Russell County, Sec. 11 Twp. 14S Rge. 13 (E) 13 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. **SE $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$**
 Lease Owner **J. F. Mergen**
 Lease Name **Annie Boller** Well No. **1**
 Office Address **Wichita, Kansas**
 Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**
 Date well completed **April 16** 19 **48**
 Application for plugging filed **April 16** 19 **48**
 Application for plugging approved **April 16** 19 **48**
 Plugging commenced **April 16** 19 **48**
 Plugging completed **April 16** 19 **48**
 Reason for abandonment of well or producing formation **Dry Hole**



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production..... 19.....
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? **Yes**

Name of Conservation Agent who supervised plugging of this well **C. D. Stough**
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	203'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Heavy mud circulated top to bottom
Wood plug set at 200 feet and dumped 15 sack cement
Wood plug set at 20 feet and dumped 10 sack cement to bottom of cellar

APR 27 1948

(If additional description is necessary, use BACK of this sheet)
 Correspondence regarding this well should be addressed to **Iron Drilling Company**
 Address **1206 Philtower Building, Tulsa, Oklahoma**

STATE OF **Oklahoma**, COUNTY OF **Tulsa**, ss.
Herrick Laboock (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) **Herrick Laboock**
1206 Philtower Building, Tulsa, Oklahoma
 (Address)

SUBSCRIBED AND SWORN to before me this **22** day of **April**, 19 **48**

B. Michal
 Notary Public.

My commission expires **Feb. 28, 1952**

21-871-8
 9-4
PLUGGING
 FILE SEC 11 T 14 R 13W
 BOOK PAGE 23 LINE 29

DRILLING RECORD

Well No. 1 Annie Boller
SE SW SW 11-14-13W
Russell County, Kansas

Casing Record

203' of 8-5/8" OD Surface
Pipe cemented with 100 sax.

Work Commenced 4-2-48
Drilling Commenced 4-5-48
Drilling Completed 4-15-48
Work Completed 4-16-48

No Oil String - Dry Hole

WELL LOG

Clay & Post Rock	0 to 40
Shale & Shells	40 to 140
Sand	140 to 155
Shale, Sand & Shells	155 to 257
Sand & Iron	257 to 585
Red Bed Shale	585 to 820
Sand & Lime	820 to 850
Lime & Shale	850 to 945
Red Bed & Shells	945 to 1080
Salt & Shells	1080 to 1360
Shale & Shells	1360 to 1850
Lime	1850 to 2000
Lime & Shale	2000 to 2130
Lime	2130 to 2200
Lime & Shale	2200 to 2320
Lime	2320 to 2330
Lime Sand	2330 to 2500
Broken Lime & Shale	2500 to 2635
Shale	2635 to 2645
Lime	2645 to 2985
Shale	2985 to 3010
Lime	3010 to 3253
Lime & Shale	3253 to 3347
Lime	3347 to 3395 TD - Plugged & Abandoned 4/16/48.

C E R T I F I C A T I O N

State of Oklahoma, County of Tulsa, SS

I, Herrick Babcock, Partner of Iron Drilling Company, Certify that the accompanying is a true and correct log of the above described well.

Signature Herrick Babcock

Subscribed to and Sworn before me this 23rd day of April, 1948.

My commission expires Feb. 28, 1952.

B. Michal
Notary Public

PLUGGING
FILE SEC-11-T-14-R-132
BOOK PAGE 73 LINE 79