


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-167-00193-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Russell County, Sec 10 Twp 14 Rge 13 (E) (W) X  
Location as "NE/CNWxSWx" or footage from lines SW SW SW  
Lease Owner Morgenstern & Spector  
Lease Name Lewis No. 1 Well No. \_\_\_\_\_  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 1-7-54 19\_\_\_\_  
Application for plugging filed May 25, 1956 19\_\_\_\_  
Application for plugging approved May 29, 1956 19\_\_\_\_  
Plugging commenced May 30, 1956 19\_\_\_\_  
Plugging completed June 3, 1956 19\_\_\_\_  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production XXXX May 1956  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt  
Producing formation Tarkio Depth to top 2389' Bottom 2390 Total Depth of Well 2390 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	186.53'	None
				5 1/2" OD	2389'	1634 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into TD 2390'. Plugged off bottom sand with chat to 2375' and dumped 5 sacks cement with dump bailer. Shot 5 1/2" casing off 1634'. Pulled pipe out of hole. Squeezed hole with 15 sacks gel mud and 85 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Co.  
Address Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Morgenstern & Spector (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morgan Spector  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of June 1956

My commission expires Dec 1, 1959  
Eddie Crady Notary Public.

PLUGGING  
FILE SEC 10 T 14 R 13W  
BOOK PAGE 66 LINE 15

06-11-56


15-167-00193-00-00-  
 WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 503 East Murdock, Wichita, Kansas

Company- KESSLER & SCHMIDT  
 Farm- Lewis No. 1

SEC. 10 T. 14 R. 13W  
 SW SW SW

Total Depth. 2390'  
 Comrn. 1-1-54 Comp. 1-7-54  
 Shot or Treated.  
 Contractor, Mast Drilling, Inc.  
 Issued. 2-27-54

County Russell  
 KANSAS



CASING:  
 5" 2389'

Elevation. 1796

Production. 25 Bbls. & 10 wtr.

Figures indicate Bottom of Formations.

cement	188
shale	255
sand	275
sand-shale	365
shale	480
red rock	522
red rock-shale	769
Anhydrite	805
shale-shells	1225
shale-lime	1690
lime	1815
shale-lime	1915
lime	1984
shale-lime	2334
shale	2390
Total Depth	

Tops:	
Grandhaven	2318
1st Tarkio	2331
2nd Tarkio	2348

**PLUGGING**  
 FILE SEC. 10 T. 14 R. 13W  
 BOOK PAGE 66 LIVE 15