

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-167-00177-00-01
WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Russell County. Sec. 10 Twp. 14 Rge. 13W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines SW NW SW
Lease Owner Icer Addis
Lease Name BOLLER Well No. 1
Office Address 120 Maple St - Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-12- 1954
Application for plugging filed 3-18- 1954
Application for plugging approved 3-18- 1954
Plugging commenced 3-19-54 1954
Plugging completed 3-22-54 1954
Reason for abandonment of well or producing formation Dry hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2387 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Arkio</u>				<u>5 1/2</u>	<u>2390</u>	<u>1603 7 1/2 5 1/2 O.D.</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 2387' to 2340' Dumped 5 sks cement from 2340' to 2300'
Filled hole with mud to 200' Put in 10' rock bridge to 190' 20 sks cement from
190' to 130' filled with mud from 130' to 35' Put in 5' rock bridge to 30' Filled
with cement from 30' to top of surface pipe.

Name of Plugging Contractor Jayhawk Well Servicing Co
Address Russell, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
Icer Addis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Icer Addis
(Address) Russell, Kansas

SUBSCRIBED AND SWORN TO before me this 21 day of January, 1954
B. M. M. M. M. M.

My commission expires 4/10/58 Notary Public.

24-7368-5 3-53-20M

PLUGGING
FILE SEC 10 - 14 - 13W
PAGE 20 INFO 23

06-22-54

15-167-00177-00-01

OPERATOR: Icer Addis
Russell, Kansas

CONTRACTOR: Mast Drilling, Inc.
Russell, Kansas

BOLLER # 1
SW/4 NW/4 SW/4
Sec. 10, Twp. 14, R. 13,
Russell County, Kansas

COMM: 1-8-54
and
COMP: 1-15-54

5 1/2 2386' with
125 day

FORMATION

DEPTH

Surface Clay - Rock	40
Clay - Shale	195
Blue Shale	200
Shale	263
Sand	325
Shale	360
Sand	398
Shale	420
Red Rock	731
Anhydrite	817
Shale - Shells	1430
Lime - Shale	1663
Lime	1355
Shale - Lime	1907
Lime	1965
Shale - Lime	1970
Shale - Lime	2337
Shale	2347
Coring	2387
TOTAL DEPTH	2387

STATE OF KANSAS

COUNTY OF RUSSELL

I hereby certify that the above information is true and correct
to the best of my knowledge.

Louis M. Mai

Subscribed and sworn to before me this 23 day of January, 1954.

Samuel J. Seaman
Notary Public

My Commission Expires: 3/27/57

