


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Russell County. Sec. 7 Twp. 14 Rge. 13E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
SW SW NW
Lease Owner Icer Addis
Lease Name SCHMIDT Well No. 1
Office Address P.O. Drawer 8038 Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed 7-16- 19 79
Application for plugging filed 7-16 19 79
Application for plugging approved 7-16 19 79
Plugging commenced 7-16 19 79
Plugging completed 7-16 19 79
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3334
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug @ 390' and cemented by Halliburton w/40 sx 50/50 pozmix, 3% Gel thru drill pipe
Top plug @ 40' w/solid bridge of $\frac{1}{2}$ sack hulls and 12 sacks cement. 3 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 1 1979 08-01-79

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke Drilling Co., Inc.
Box 823 - Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.
Bill Draney (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of July, 19 79

Loucky M. Haque
Notary Public.

My commission expires 4-11-1982

DRILLERS' WELL LOG

DATE COMMENCED: July 9, 1979
 DATE COMPLETED: July 16, 1979

Loc: Aditis
 SECTION 7 1
 SW 34 11
 Sec. 7 - T14S - R13W
 Russell County, Ka.

0	-	63	Surface Soil, Post Rock
63	-	261	Shale
261	-	309	Sand & Shale
309	-	314	Hard Sand
314	-	362	Sand & Shale
362	-	824	Shale
824	-	852	Anhydrite
852	-	2354	Shale & Lime
2354	-	2364	Lime
2364	-	2370	Sand
2370	-	2386	Lime
2386	-	2677	Sand, Shale, Lime
2677	-	2729	Lime
2729	-	2932	Shale
2932	-	2949	Lime & Shale
2949	-	2961	Lime
2961	-	2992	Shale
2992	-	3249	Lime
3249	-	3334	Lime, Shale RED

ELEVATION: 1828 K.B.

FORMATION DATA

Anhydrite	824
Grandhaven Lime	2354
1st Turcio Sand	2364
Dover Lime	2370
2 nd Turcio Sand	2386
Turcio Lime	2423
3rd Turcio Sand	2456
Howard	2631
Tropola	2677
Huebner	2727
Toronto	2949
Douglas	2961
Lansing - K.C.	2988
Base - K. C.	3249
Conglomerate	3300
RED	3334

STRAPE TEST: Set
 used 8 7/8" pipe, 28 #
 at 982' w/200' scales
 60/40 porous, 2 1/2 gal,
 3 1/2 cc.

AFFIDAVIT

State of Kansas
 County of Barton) ss.

Bill Draney, of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 17 day of July, 1979

Lois M. Hagan
 Notary Public

My Comm. Expires: April 11, 1982

RECEIVED
 STATE COMMISSION
 AUG - 1 1979
 CONSERVATION DIVISION
 Wichita, Kansas