

15-167-30133-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Russell County. Sec. 7 Twp. 14S Rge. (X) 13 (W)

Location as "NE/CNW&SW&" or footage from lines NW NE NW
Lease Owner Jay-Bee Oil Company, Inc.
Lease Name Schmidt "A" Well No. 1
Office Address 511 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 19, 1965
Application for plugging filed October 19, 1965
Application for plugging approved October 19, 1965
Plugging commenced October 19, 1965
Plugging completed October 19, 1965
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3303 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 350 feet. Followed by wooden plug and 1/4 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 4 sacks cement.

Stamp: OCT 27 1965 10-27-65

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 1965

[Signature]
Betty Brandt Notary Public.

My commission expires April 30, 1967

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Jay-Bee Oil Company, Inc. DRILLING COMMENCED: October 12, 1965
 511 Union Center
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: October 19, 1965
 412 Union Center
 Wichita, Kansas

CASING RECORD: 19 Jts. 379' 8-5/8" cemented with 225 sacks LOCATION: Schmidt "A" No. 1
 NW NE NW
 Section 7-14S-13W
 Russell County, Kansas

0 - 35	Lime & clay
35 - 379	Shale & lime
379 - 825	Shale & red bed
825 - 856	Anhydrite
856 - 1514	Shale & shells
1514 - 1728	Lime & shale
1728 - 2060	Lime
2060 - 2252	Lime & shale
2252 - 2371	Shale & lime
2371 - 2405	Sand
2405 - 2717	Lime & shale
2717 - 2950	Lime
2950 - 2995	Lime & shale
2995 - 3250	Lime
3250 - 3300	Lime with chert
3300 - 3303	Lime & shale
3303	Rotary Total Depth

NOTARY PUBLIC
 STATE OF KANSAS
 OCT 27 1965
 BUTLER COUNTY, KANSAS

I hereby certify the foregoing statement to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves President

STATE OF KANSAS)
) SS:
 BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 22nd of October, 1965.

My commission expires:
 April 30, 1967

Betty Brandt
 Betty Brandt Notary Public