


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-167-00151-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Russell County. Sec. 6 Twp. 14 Rge. 13 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW NE
Lease Owner Dizdar Investment Company
Lease Name Witt Well No. 1
Office Address McAllen, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 8 19 51
Application for plugging filed May 8 19 51
Application for plugging approved May 8 19 51
Plugging commenced May 8 19 51
Plugging completed May 8 19 51
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3353 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	127'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Cementers plug and one-half sack of hulls was placed at 120'. Fifteen sacks of cement was mixed and dumped on top of plug. Casing was filled with mud to depth of 40'. Cementers's plug and one-half sack of hulls was placed at 40' depth. 40 sacks of cement was mixed and placed from depth of 40' to surface.

05-21-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Glenn R. Nye Drilling Company
Address Drawer 30, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
Glenn R. Nye (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glenn R. Nye
Drawer 30 Hays Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of May, 19 51.

My commission expires May 9, 1953

Notary Public.

PLUGGING
REC 6 T 14 R 13
PAGE 20 LINE 42

15-167-00151-00-00

Company: Dizdar Investment Company
Contractor: Glenn R. Nye Drilling Company
Commenced: April 27, 1951
Completed: May 8, 1951

Farm: Witt No. 1
Location: NWSW NE Sec. 6-11-13 W
Russell County, Kansas
Casing Record: 8 5/8" set at 127'

(Figures below indicate bottoms)

shale and shells	30	
surface clay and sand shale	100	
shale and shells	127	
shale, shells and clay	180	
shale and clay	380	
sand and shale	520	
shale and sand	660	
red bed	830	
anhydrite	840	
anhydrite	867	
shale and shells	1120	
shale and shells	1290	
salt and shale	1435	
salt and shale	1480	
shale and shells	1545	
lime and shale	1570	
lime and shale	1715	
lime and shale	1855	Top of Fort Riley
lime and shale	1915	1760
lime and shale	1990	
lime and shale	2005	
shale and shells	2080	
shale and lime	2195	
shale and lime	2310	
shale and lime	2450	Top of Torkio 2430
shale and lime	2465	
shale and lime	2625	
shale and lime	2750	
lime and shale	2770	Top of Topeka 2728
lime and shale	2845	
lime and shale	2895	
lime and shale	2952	Top of Dodge 2928
lime and shale	3020	Top of Hebner 2960
lime and shale	3065	Top of K. C. Lansing
lime	3102	3024
lime	3135	Top of Conglomerate
lime	3175	3314
lime	3221	
lime	3226	
lime	3270	
lime	3310	Top of Arbuckle 3343
lime	3340	
lime	3353	T. D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Glenn R. Nye

STATE OF KANSAS)
) SS
ELLIS COUNTY)

Subscribed to and sworn to before me, a notary public, in and for said County and State this 11 day of May, 1951.

Jean [Signature]
Notary Public

My Commission Expires. May 1, 1953

PLUGGING
FILE SEC 6 T 14 R 124
BOOK PAGE 80 LINE 40