


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Russell

County. Sec. 12 Twp. 14S Rge. 14W (E) (W)

Location as "NE/CNW&SW" or footage from lines. NW NW SW

Lease Owner A. Scott Ritchie & Don C. Slawson

Lease Name Brandenburg "B"

Well No. 1

Office Address 352 N. Broadway, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed October 28, 1964 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced October 28, 1964 19

Plugging completed October 28, 1964 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Depth to top Bottom Total Depth of Well 3390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8" 279' circulated with cement. Sanded hole back to 3250' & dumped 5 sacks cement with dump bailer. Pulled pipe. Mudded hole to 280' set rock bridge; displaced 25 sacks cement. Mud to 40'; set rock bridge & displaced 10 sacks cement, cementing to base of cellar.

RECEIVED
U.S. DEPT. OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

MAR 4 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

A. Scott Ritchie

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

A. Scott Ritchie

(Address)

305 Union Center Bldg
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 1966

BARBARA A. CRAFT

Notary Public.

My commission expires

BARBARA A. CRAFT, Notary Public
My commission expires Sept. 11, 1969

WELL LOG

Company: Ritchie - Slawson
352 N. Broadway
Wichita, Kansas

Farm: Brandenburg 'B' #1
NW NW SW Section 12-14S-14W
Russell County, Kansas

Total Depth: 3270' Elevation: 1835 K.B.

Commenced: September 4, 1964
Completed: September 15, 1964

Contractor: Slawson Drilling Company, Inc.

Casing: 277' of 8 5/8" with 190 Sacks cement
3263' of 5 1/2" with 65 Sacks cement

0-277	Lime
277-367	Shale & Shells
367-525	Shale & Shells & Sand
525-815	Red Bed & Shells
815-1515	Shale
1515-2053	Lime
2053-2146	Shale
2146-2698	Shale & Lime
2698-2924	Lime
2924-2927	Shale
2927-2958	Lime
2958-2985	Shale
2985-3205	Lime
3205-3264	Lime & Shale
3264-3270	Lime
3270	R.T.D.

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1964


CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I Donald C. Slawson, of the Slawson Drilling Company, Inc.,
upon oath state that the above and foregoing is a true and
correct copy of the log of the Brandenburg 'B' #1 well.


Donald C. Slawson

Subscribed and sworn to before me this 14th day of October, 1964.


Ella Priess, Notary Public

My Commission Expires:
August 25, 1968