


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Russell County. Sec. 12 Twp. 14 Rge. 14 (E) (W)  
Location as "NE/CNW&SW" or footage from lines SW NW NW  
Lease Owner Leben Drilling, Inc.  
Lease Name Brandenburg Well No. 1  
Office Address P. O. Box 186 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 6-8-65 19\_\_\_\_  
Application for plugging approved 6-9-65 19\_\_\_\_  
Plugging commenced 7-2-65 19\_\_\_\_  
Plugging completed 7-15-65 19\_\_\_\_  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2393 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	202	None
				4 1/2	None	1501

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Cleaned out cellar. Working pipe - 16" tension.

Pumped cement plug to 2200'.

Run steel line at 1446'. Working pipe. Shot would not go down - 18" tension.

Working pipe. Spudded on bridge at 1446'. Moved bridge to 1506'.

Pumping on bridge. Spudded on bridge. Working pipe. Shot pipe at 1500'.

Pulling pipe.

Squeezed well with 10 sacks of mud and 70 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of July, 1965

My commission expires May 27, 1969

[Signature]  
Notary Public.

XERO COPY

XERO

DRILLER'S LOG

COMPANY: Leben Drilling, Inc.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: BRANDENBURG #1  
 LOCATION: SW NW NW Sec. 12-14S-14W  
 RUSSELL COUNTY, KANSAS  
 COMMENCED: 3-21-63  
 COMPLETED: 3-25-63

0	25	Surface Clay
25	202	Sand, Shale, Shells
202	450	Shale
450	765	Redbed
765	790	Anhydrite
790	1300	Shale & Redbed
1300	1780	Shale & Shells
1780	2312	Lime & Shale
2312	2357	Core #1.
2357	2393	Lime & Shale
	<u>2393</u>	<u>Rotary Total Depth - Set 4 1/2" casing</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 22 1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" used surface casing @ 202' Cemented with 145 sacks Sunset.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Brandenburg #1, located SW NW NW of Section 12, Township 14 South, Range 14 West, Russell County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 )  
 COUNTY OF BARTON ) SS

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 26th day of March, 1963.

Ulanda Nichols  
 Ulanda Nichols, Notary Public

My Commission Expires:  
 April 1, 1963