


15-167-00171-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 34 Twp. 14 Rge. 11 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW
Lease Owner Duke & Wood Drilling Company, Inc.
Lease Name Turner Well No. 1
Office Address Box 194, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 3, 19 51
Application for plugging filed November 3, 19 51
Application for plugging approved November 3, 19 51
Plugging commenced November 3, 19 51
Plugging completed November 3, 19 51
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3269 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	235.46	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 210 ft. Set plug @ 210 ft., dumped 15 sacks
cement on same, filled hole to 40 ft., set plug @ 40 ft. Dumped 10 sacks
cement, filled to bottom of cellar .

11-13-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Duke & Wood Drilling Company, Inc.
Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Cecil M. Olson (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of November 19 51

Dean Cooley Notary Public.

My commission expires April 29, 1953.

FILED 34:10:11W
BOOK 2011W 29

15-167-00171-00-06

WELL LOG
Turner #1
SW SW SW Section 34-14-11W
Russell County, Kansas

Started October 23, 1951
Completed 3rd of November, 1951

Elevation 1725 R. B1
Anhydrite 590 (-1135)
Heebner 2784 (-1059)
Lansing 3893 (-1167)
Conglomerate 3216 (-1491)
Arbuckle 3268 (-1543)

0-105	Surface clay, post rock
105-231	Sand, shale, red bed and red rock
231-590	Red rock, shale, sand & iron
590-610	Anhydrite
610-1310	Shale, shells & red bed
1310-1480	Shale, shells & broken lime
1480-1730	Shale and lime
1730-1875	Lime
1875-2135	Shale and lime
2135-2410	Shale & Lime
2410-2585	Shale & Lime
2585-2720	Lime
2720-2900	Lime and shale
2900-3030	Lime
3030-3139	Lime
3139-3216	Lime
3216-3268	Conglomerate
3268-3269	Arbuckle
3269	TOTAL ROTARY DEPT H


A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton, SS.

I, Lynn O. Duke of the DUKE & WOOD DRILLING COMPANY, INC. being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.


Vice-President

Subscribed and sworn to before me this 12th day of November 1951.


Notary Public

My commission expires: April 29, 1953.

FILE NO. 34-14-11W
BOOK PAGE 144-144

RECORDED
NOV 13 1951