

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION Rev. 12-15-80

OCT - 1 1981

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Russell Co., Ks. SEC. 30 TWP. 14S RGE. 11 NEW
Location as in quarters or footage from lines:
SE NW NW

Lease Owner H & K Oil Company, % of Orville Kaufman
Lease Name Lester Well No. # 1
Office Address R.R. # 1, Great Bend, Ks 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 9-27-81
Application for plugging filed 9-27-81
Plugging commenced 9-27-81
Plugging completed 9-27-81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3207

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 720' with 70 sks. cement thru Drill Pipe.

Middle Plug @ 240' with 40 sks. cement thru Drill Pipe.

Top Plug @ 40' with 1/2 sks. Halls & 10 sks. cement.

5 sks. cement in Rat Hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Company, Inc.
P.O. Box 823, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton Co., KS ss.

Leonard Williamson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
Box 823, Great Bend, Ks 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 29 day of September, 19 81

Dorothy M. Wagner
Notary Public.

My Commission expires: April 11, 1982

15-167-21780-00-00

RECEIVED
STATE CORPORATION COMMISSIONDRILLERS' WELL LOG

15-167-21780-00-00

DATE COMMENCED: September 21, 1981
DATE COMPLETED: September 27, 1981H & K Oil Co. CONSERVATION DIVISION
Lester # 1 Wichita, Kansas
SE NW NW
Sec. 30-T14S-R11W
Russell County, Ks.

ELEVATION: 1707 KB

FORMATION DATA

0 - 250'	Surface Soil, Shale, Red Bed
250 - 570'	Red Bed, Shale
570 - 598'	Anhydrite
598 - 1260'	Shale
1260 - 2508'	Lime & Shale
2508 - 2518'	Shale
2518 - 2759'	Lime
2759 - 2777'	Shale & Lime
2777 - 2791'	Lime
2791 - 2843'	Shale
2843 - 2853'	Lime & Shale
2853 - 3122'	Lime
3122 - 3197'	Lime, Shale, Congl.
3197 - 3207'	Dolomite
3207'	RTD

Anhydrite	570
Severy	2508
Topeka	2518
Heebner	2759
Toronto	2777
Douglas	2791
Br. Lime	2843
Lansing-KC	2853
Base KC	3122
Conglomerate	3141
Arbuckle	3197
RTD	3207

SURFACE PIPE: Set New
8 5/8" pipe @ 250' with
165 sks. 50/50 Pozmix,
2% gel., 3% c.c.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ssLeonard Williamson of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.Subscribed and sworn to before me this 29 day of September 1981.

My Comm. Expires:

4-11-82Clarence M. Hager
Notary Public