

15-167-21374-00-06

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Russel SEC. 29 TWP. 14 RGE. 11w E/W  
 Location as in quarters or footage from lines:  
SE NE NW


Lease Owner Saline Bason Petroleum  
 Lease Name Ethel Herber Well No. 3  
 Office Address 725 W. Ash Salina Kans. 67401  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed 3/7/80  
 Application for plugging filed 5/18/83  
 Plugging commenced 6/2/83  
 Plugging completed 6/10/83  
 Reason for abandonment of well or producing formation Dry

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Marion Schmidt

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 2945

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	223	8 5/8		
		0	2944	5 1/2		1397

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Cemented bottom with Allied cementers With 50 sx. common cement  
Pump plug down to 2100

Pumped top with Allied Cementers with 5 sx. hulls 15 jell and 165  
sx. 50-50 pozmix cement with 4% jell & 3% C.C.

STATE CORPORATION COMMISSION

JUN 14 1983

CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling  
Box 206 Geneseo Kansas 67444

STATE OF Ks COUNTY OF Rice, ss.  
G.A. Nicholas (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) G.A. Nicholas  
 (Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 13<sup>th</sup> day of June, 1983

Steven K. Prickett  
 Notary Public.

My Commission expires: \_\_\_\_\_

