

4-060381

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,829-00-00

E2 SW SW /4 SEC. 09, 14 S, 17 W
660 feet from S section line
4290 feet from E section line

Operator license# 5363 Lease Regina well # 6

Operator: Berexco, Inc. County Ellis

Address: 970 Fourth Financial Center Well total depth 3600 feet ^{117.00}
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Duke Drilling Company License# 5929

Address: 310 W. Central - #117 - Wichita, Kansas 67202

Company to plug at: Hour: 8:30A.M. Day: 18 Month: March Year: 93

Plugging proposal received from: Jay Schneider

Company: Duke Drilling Company Phone: 316-267-1331

Were: Order 215 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:30A.M., Day: 18, Month: March, Year: 93

Actual plugging report:
1st. plug at 3533' w/ 25 sxs. - Arbuckle at 3543'.
2nd. plug at 1230' w/ 25 sxs. - Anhydrite 1208' - 1242'.
3rd. plug at 590' w/100 sxs. - Dakota 286' - 586'.
4th. plug at 315' w/ 40 sxs. - Surface pipe to 264'.
5th. plug at 40' w/ 10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2011 GL

I did NOT / did not [X] observe the plugging.

DATE 3-23-93

37497

3-18

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1993
03-23-1993
CONSERVATION DIVISION
WICHITA, KANSAS

(agent)

Form CP-2/3

JUN 23 1993 11 37 AM '93