

6-28  
4-060703

15-051-301608-00-00

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15- - 8-20-62

SW SE SE/4 SEC. 09, 14 S, 17 W  
330 feet from S section line  
990 feet from E section line

Operator license# 5363

Lease: Simon Well # 3

Operator: Berexco, Inc.

County: Ellis

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 3569 feet  
Conductor Pipe: 0 inch @ 0 ft  
Surface pipe 8% Inch @ 188 ft

115.99

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Co Tools License# \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: 2:00 P.M. Day: 28 Month: June Year: 1995

Plugging proposal received from: Ted Crawford

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 350 sxs. 60/40 posmix - 10% gel and hulls. Plug through tubing. Emergency permission to plug with rig over hole.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 4:45 P.M., Day: 28, Month: June, Year: 1995

Actual plugging report: 8 5/8" to 188' with 145 sxs. 4 1/2" to 3540' with 125 sxs. Squeezed at 765' w/150 sxs. Squeezed at 908'-1031' w/150 sxs. Squeezed at 1511' w/10 sxs. Holes in casing from 1495'-2700' confirmed by testing with tubing and packer. Ran tubing to 2470'. Pumped 60 sxs. cement w/300# hulls. Pulled tubing to 1500' and pumped 100 sxs. cement w/400# hulls. Pulled tubing to 800' and pumped 25 sxs. cement w/100# hulls with cement to surface. Pulled tubing and tied onto annulus. Pumped 35 sxs. cement w/100# hulls. Max.P.S.I. 400#. S.I.P. 200#. Tied onto production casing and pumped 12 sxs. cement. Max.P.S.I. 500#. S.I.P. 500# & locked up.


Remarks: Allied Cementing.

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD  Anhy.plug: YES  NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC , NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_

Plugged through TUBING , CASING \_\_\_\_\_ Elevation: 2011 GL

I did  / did not  observe the plugging.

  
(agent)

07-21-1995  
JUL 23 1995

Form CP-2/3

INVOICED

DATE 7-25-95

INV. NO. 43156