

4 060003

7-4

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-063-21,270-00-00

NE NE, SEC. 25, T 14s S, R 27 W/EX

TECHNICIAN'S PLUGGING REPORT

4630 feet from S section line

600 feet from E section line

Operator License # 5663

Lease Name Groom Well # 1

Operator: Hess Oil Co.

County Gove 141.90

Name & Address P.O. Box 1009

Well Total Depth 4366 feet

Wichita, KS 67460

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita, KS

Company to plug at: Hour: 6:00 P.M. Day: 04 Month: July Year: 19 89

Plugging proposal received from LaVon Urban

(company name) Abercrombie Drilling (phone) 316-262-1841

were: Space all plugs with heavy mud. Plugs to be set at 1950' w/20sxs, 927' w/100sxs, 260' w/40sxs., 40' w/10sxs. 15sxs in rat hole and 10 sxs in mouse hole.

Order 195 sxs. 60/40 posmix. 6%gel, 1/4# flowcel or celloflake per sx. of cement.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

Operations Completed: Hour: 6:00PM Day: 04 Month: July Year: 1989

ACTUAL PLUGGING REPORT Plugs spotted through drill pipe and spaced with heavy drilling mud.

1950' w/20sxs. Anhydrite 1928-1967' Arbuckle not reached

927' w/100sx. Dakota 627-927' Allied Cementing

260' w/40 sx. Surface pipe set at 207'

40' w/10 sx.

15 sx in rat hole and 10 sx in mouse hole

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ (If additional description is necessary, use BACK of this form.)

DATE 7-13-89

Signed Herb Deines  
(TECHNICIAN)

INV. NO. 25326

7-4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

JUL 12 1989  
68-2170