

8 031492

1-23

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,368 - 00-00

NE NE NE, SEC. 24, T 14 S, R 27 W#E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5663

Lease Name Ward Well # 1

Operator: Hess Oil Co.

County Gove 143.32

Name & Address: Box 1009

Well Total Depth 4410 feet

McPherson, Ks. 67460

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Mallard J V Inc License Number 49588

Address McPherson, Ks.

Company to plug at: Hour: PM Day: 23 Month: Jan Year: 19 91

Plugging proposal received from Arnie Hess

(company name) Mallard (phone)

were: 8 5/8 set at 211 w/145 sks cwc, circ. hole w/no less than 36 vis mud w/no

loss or gain of fluids. Balance plugs w/mud Order 200 sks 60/40 poz 6% gel 3% cc
8 5/8 w.p. allied Cement Co.

RECEIVED
STATE CORPORATION COMMISSION

MAR - 5 1991

Plugging Proposal Received by Carl Goodrow (TECHNICIAN) CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 8:00PM Day: 23 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe w/25 sks at 1960

100 sks at 930 w/hulls

40 sks at 260

10 sks at 40 w/w.p.

Circ. 15 sks in rathole.

Circ 10 sks in mousehole.

Remarks: Elev. 2497 Anhy 1955 - 95

(if additional description is necessary, use BACK of this form.)

INVOICED

(if not observed) observe this plugging.

DATE 3-11-91

INV. NO. 31108

1-23

Handwritten signature

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow