

6-100439

9-14

42
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,405-00-00

C SE NW /4 SEC. 22, 14 S, 27 W
3300 feet from S section line
3300 feet from E section line

Operator license# 30269

Lease Richardson well # 1

Operator: Argent Energy, Inc.

County Gove

Address: 110 South Main
Suite 510
Wichita, Kansas 67202-3745

Well total depth 4382 feet ^{142.42}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 276 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Rodney Farr

Company: Murfin Drilling Company phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ <u>1945</u> feet with	<u>25</u> sacks	Rat hole: <u>15</u> sacks
2nd plug @ <u>960</u> feet "	<u>100</u> "	Mousehole: <u>10</u> sacks
3rd plug @ <u>330</u> feet "	<u>40</u> "	
4th plug @ <u>40</u> feet "	wiper plug & 10 sx	

NOV 12 1991

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 6:45 am, Day: 14, Month: September, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2485 GL, Anhydrite depth: 1944 - feet

Did NOT penetrate Arbuckle, cemented by Allied

I did not [X] observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

INVOICED
DATE 11-21-91
33817

Int. S.