

6 070910

4-4  
API NUMBER 15- 063-21,382-00-00

327

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW-SE, SEC. 19, T 14 S, R 27 W  
330 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name TJaden Well # H #1

Operator: Slawson Exploration Co.

County Gove 65.97

Name & Address 104 So. Broadway #200 Inc.

Well Total Depth 2030 feet

Wichita, Ks. 67202-14165

Conductor Pipe: Size 0 feet

Bob Jenkins

Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L. D. Drilling License Number 6039

Address Great Bend, Ks.

Company to plug at: Hour: AM Day: 4th Month: April Year: 19 91

Plugging proposal received from Greg Davidson

(company name) L. D. Drilling (phone)

were: 8 5/8 - 384 ft. s.p. cwc w/200 sks 60/40 poz 2% gel 3% ca cl. By Allied

Cement. Miss well - Elv. 2480 - Anhy 1926. No circulation problems. Mud

condition 36 vis 9.2 weight 11 water loss. Proposal Circulate hole.

Mud 42-45 viscosity. 190 sks 60/40 poz 6% gel 3% ca cl. Spot with

drill stem. Heavy mud between all plugs. 25 sks at 1930. 100 sks w/1 sk f

f.c. at 855 ft. 40 sks at 430 ft. 10 sks at 40 ft. and 15 sks in rathole.

Circ. Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN) MJS

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 2:30AM Day: 4 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Slawson ordered 190 sks 60/40 poz

6% gel 3% ca cl. Circulated hole 42-45 viscosity. Spotted cement with

STAT. 04-22-91 crill stem w/heavy mud between all plugs.

APR 22 1991 1st plug at 1930 ft. w/25 sks cement.

2nd plug at 855 ft w/100 sks cement w/1 sk f.c.

3rd plug at 430 ft. w/40 sks cement

4th plug at 40 ft w/10 sks cement

15 sks rathole (circulate)

Remarks: Allied Cement.

(if additional description is necessary, use BACK of this form.)

INVOICED

to observe this plugging.

DATE 4-29-91

INV. NO. 3170.6

Signed Marion J. Schmidt (TECHNICIAN)