

4 050096

3-21

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,178-20-00
E/2 SW, SEC. 16, T. 14 S, R 27 W/Ex

1320 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Albin L Well # 1

Operator: Viking Resources Inc.

County Gove 143.00

Name & Address 105 S. Broadway

Well Total Depth 4400 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 237

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: PM Day: 21 Month: March Year: 19 91

Plugging proposal received from Terry Richardson

(company name) Viking Resources Inc. (phone)

were: Order 350 sks 65/35 poz 8% gel 1/2 lb c.f. /sk and

500 lbs. hulls.

Well Record: 8 5/8 set at 237 ft. w/165 sks.

4 1/2 set at 4398 w/250 sks (Perfs 3979 - 81 and 3984 - 87

D.V. set at 1968 ft. w/350 circulated to surf.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:15PM Day: 21 Month: March Year: 19 91

ACTUAL PLUGGING REPORT Tied onto 4 1/2 casing pumped 240 sks 65/35 poz

8% gel 1/2 lb c.f. /sk w/300 lbs. hulls. Sq at 700 max psi and 600 shut in

psi. Sq 110 sks down backside w/500 max psi and 300 shut in psi.

RECEIVED STATE CORPORATION COMMISSION

APR 04 1991

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

If additional description is necessary, use BACK of this form.)

DATE I did / observe this plugging.

INV. NO. 31504

3-21

MAY 03 1991

Signed Marvin D. Miller (TECHNICIAN)
Marvin Miller