

6 030530

API NUMBER 15-063-20,937-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/4 NW/4 SEC. 16, T 14 S, R 27 W/4

4950 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067 & 6390

Lease Name RICHARDSON Well # 1

Operator: DAMAR RESOURCES INC. & MCDONALD-County GOVE

141.70

Name & Address WALLACE PETROLEUM CO. INC.

Well Total Depth 4360 feet

Box 70

Conductor Pipe: Size _____ feet

HAYS, KANSAS 67601

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor DREILING OIL, INC. License Number 5145

Address VICTORIA, KANSAS 67671

Company to plug at: Hour: _____ Day: _____ Month: 7 Year: 19 85

Plugging proposal received from OFFICE

(company name) DREILING OIL, INC. (phone) _____

were: 8 5/8 SET @ 304' CONDITION HOLE W/ NO LESS THAN 36 VLS. MUD
WITH NO LOSS OR GAIN OF FLUID. SPOT CEMENT PLUGS W/ DRILL PIPE.
ORDER 200 SX. 60/40 PPT 6 BAGEL 3 BCC. 8 5/8 W.P. 1 SX. CELLO FLAKE

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:30 PM Day: 22. Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 1980 BREAK CIRC. DISPLACE 2544 CMT. MIX
LAY DOWN D.P. TO 925' DISPLACE 100 SX. CMT MIX. + 1 SX. CELLO FLAKE
LAY DOWN D.P. TO 310' DISPLACE 40 SX. CMT. MIX. LAY DOWN D.P.
PUSH 8 5/8 W.P. TO KELLY DEPTH FILL HOLE TO BASE OF CELLAR W/ 10 SX.
CMT. MIX. DISPLACE 15 SX. CMT MIX. IN BATHOLE - 10 SX. IN HOUSEHOLE
W/ JOINT OF PIPE PLUG COMPLETE

Remarks: _____

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 06 1985

INV. NO. 9325

RECEIVED
AUG 5 1985

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
AUG 5 1985
08-05-85
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84