

6 030709

API NUMBER 15-063 - 20282-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CNLM 1/2 NW SEC. 15, T. 14 S., R. 27 (W)

4620 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name LONG Well # 1

Operator: CHIEF DRUG. CO INC.

County GOVE 141.21

Name & Address 905 CENTURY PLAZA

Well Total Depth 4345 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE, KANSAS

Company to plug at: Hour: PM Day: 9 Month: 4 Year: 19 86

Plugging proposal received from BILL FULLS

(company name) KELSO CASING. (phone) _____

were: 8 5/8 @ 305 w/185 sx. 4 1/2 @ 4329 7 sx. 4304 FLOAT 26' SHOE JOINT

4 CENTRALIZERS & BASKET @ 1960 ORDER SAND & CEMENT. SHOT &

STRIP PIPE ORDER 180 SX. 60/40 POLY GEL 3% @ 40 SX. GEL 4 SX. HULLS

ALLIED CEMENT CO. WALKER WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 PM Day: 9 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT SAND TO 4300' Dump 4 SX. CEMENT ON SAND W/ BAILER

SHOT & STRIPPED 2421' OF 4 1/2" CASING

HOOK ON TO 8 5/8 MIX. & PUMP 3 SX. HULLS. 32 SX. GEL - 100 SX. CEMENT MIX. +

1 SX. HULLS. 8 SX. GEL. 80 SX. CEMENT MIX. MAX. PSI 700** CLOSE IN 150 PSI

PLUG COMPLETE

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1986

04-28-86
CONSERVATION DIVISION

Remarks: _____
(If additional description is necessary, use BACK of this report.)

4-25-86

INDICATED observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)

DATE APR 29 1986

INV. NO. 13562